Items of work.	*Per.*	*Quantity.*	*Remarks.*
Irrigation Channels (right to left)—			
Earthwork (excavation)	C. yds.	45,368	
Mile and	No.	16	
Half furlong stone	,,	218	
Grade stone	,,	232	
Irrigation Sluices—			
Excavation	C. yds.	185	
Stone in chunam	C. ft.	2,849	
Burnt stone slab	S. ft.	353	
Revetment	C. yd.	37	
Iron pipe	Per foot	529	
Relieving Weirs—			
Earthwork (excavation)	C. yds.	784	
Brick in chunam	C. ft.	43,120	
Burnt stone slabs	S. ft.	3,920	
Plastering with chunam	Sqrs.	27·44	
Dry stone	C. yds.	1,176	
Syphons—			
Earthwork	C. yds.	2,572	
Stone in chunam	C. ft.	10,648	
Brick in chunam	,,	8,506	
Do arch work	,,	2,046	
Concrete	,,	160	
Burnt stone slabs	S. ft.	1,182	
Plastering with chunam	Sqrs.	50·28	
Rough stone	C. yds.	106	
Cart Bridges—			
Burnt stone slabs	S. ft.	2,100	
Burnt stone in chunam	C. ft.	880	
Pointing with chunam	Sqrs.	21·80	
Gravel	C. yds.	26·80	
Excavation	,,	150	
Cut stone work	C. ft.	1,800	
Guard stones	No.	80	

K. PRAHLADA RAO, *Offg. Exec. Engineer.*

FRENCH ROCKS DIVISION.

The 10th August 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to 10th September 1898, for constructing an aqueduct at the 7¼ mile of Chickdevarayasagar Channel for the diversion of Mosalehalla drainage, Seringapatam taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1899.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 10 A. M. to 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The Tenders should be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing an aqueduct at the 7¼ mile of Chickdevarayasagar Channel" in default of which tenders will be rejected.

5. The first acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.	Unit of work.	Rate per unit.
Aqueduct—		
Clearing site	Lump sum.	
Earthwork excavation	C. yds.	1,698
Surki concrete	C. ft.	13,945
Burnt stone in surki mortar	,,	38,218
Pointing with do	Sqrs.	157·45
Plastering with surki	,,	69·23
Rough stone work, new	C. yds.	837
Burnt stone slabs dressed	C. ft.	3,875
Cut stone work neatly dressed and fitted	,,	68
Baling water	Lump sum.	
Diversion of Channel—		
Rough stone work, new	C. yds.	1,510
Cutting draft channel, &c.	,,	3,187
Jelly packing	,,	1,136
Earthwork embankment from the stuff available from cutting	C. yds.	14,722
Turfing	Sqrs.	491·00
Diversion of Jungle Stream—		
Cutting draft channel, &c.	C. yds.	12,065

K. KRISHNAIENGAR, *Executive Engineer.*

SANITARY ENGINEER'S CIRCLE.

The 11th August 1898.

Notice is hereby given that sealed tenders will be received up to 12 noon on the 15th September 1898 by the Supervisor, Mysore Water Works Range, for the supply by contract of the undermentioned articles required for the Vani Vilas Water-supply Works of the Mysore City for the year 1898-99.

2. Tenders should be superscribed "Tenders for supply of articles for the Vani Vilas Water-supply Works for the year 1898-99.

3. Each tenderer must forward along with the tender sample of the articles that he is willing to supply. The samples should be labelled and must bear his signature and address.

4. All tenderers must specify the lowest rate for each article at which they will undertake to deliver the same at the office of the Supervisor, Mysore Water Works Range at Mysore, in such quantities as may be ordered by the Supervisor from time to time to be supplied during the year 1898-99; and all articles supplied must be of good quality and similar to the approved samples.

5. The tenders will be opened by the Supervisor, Mysore, Water Works Range at Mysore, in his office on the date and hour above named in the presence of such tenderers as may choose to attend, and submitted to the Sanitary Engineer, who is the officer to accept or reject the tenders.

6. The Sanitary Engineer does not bind himself to accept the lowest or any tender; and he may reject any tender without assigning any reason for it.

7. Schedule of articles required:—

No.	Names of articles.	Approximate quantities required during the year.	Rates to be mentioned.	Quantity of sample to be produced.
1	Kerosine oil	25 tins	Per bottle	1 bottle.
2	Tallow	400 lbs.	Per lb.	1 lb.
3	Cocoanut oil	50 bottles	Per bottle	1 bottle.
4	Linseed oil	10 do	Do	1 do
5	Charcoal	10 bags	Per bag	5 lbs.

NOTE.—The above quantities are not guaranteed.

8. The supply contracted for to commence at the beginning of October 1898.

9. Within one week of the date of the acceptance of the tender, the successful tenderer will be required to furnish a security deposit of Rs. 25 and to execute an agreement for the due performance of the contract.

STANDISH LEE,
Sanitary Engineer with the Govt. of Mysore.